



project profile

Project

Phase 1,2 & 3

Saracens FC

StoneX Stadium

Hendon

UK

System

Grasscrete GC3

Grasscrete GC2

Quantity

16,000 m²

Application



The first phase of this stadium redevelopment, undertaken in 2016, featured a 5600 m² spectator car park, constructed from 76mm thick Grasscrete GC3 paving, but within which there was an access link to a future extension. This was constructed from 150mm thick Grasscrete GC2, so as to enable access for construction traffic to those works.

The second phase of the works in 2019, focussed on the construction of parking areas closer to the stadium for outside broadcast units, with heavy loadings again calling for the updated Grasscrete GC2 to be installed, this phase required working to tight timescales leading up to the beginning of the new season.

Work then continued with Phase 3 a significant extension to the Phase 1 car parks, but during this period the works were initially affected by ground conditions and then by the Covid pandemic. With the impact on sporting fixtures due the pandemic, attention turned to a new temporary use as a drive-in cinema facility, with areas being turned over to this facility as they became available.

The completed car parks now provide for the large number of spectators at this successful rugby club, with the grassed landscape providing an ideal setting for the pre-match tradition of car boot picnics. Between matches the car parks are used for the many conferences held at the stadium.